

## **CERTIFIED SOLAR SYSTEM**

SUPPLIER: HTP, Inc. 272 DUCHAINE BLVD NEW BEDFORD , MA 02745 USA www.htproducts.com

In Accordance with: SRCC OG-300-2001-10

BRAND: SOLAR SKIES

MODEL: PR-119-64-EB

SYSTEM TYPE: Pumped, Indirect

CERTIFICATION #: 2007019C

Original Certification:

February 14, 2008

Jeruncauon.

Expiration Date: July 27, 2020


The solar system listed below has been evaluated by the Solar Rating & Certification Corporation™ (SRCC™), an ISO/IEC 17065 accredited and EPA recognized Certification Body, in accordance with SRCC OG-300, Operating Guidelines for Certifying Solar Water Heating Systems, and has been certified by the SRCC. This award of certification is subject to all terms and conditions of the Program Agreement and the documents incorporated therein by reference. This document must be reproduced in its entirety.

Description: Glazed Flat Plate, Differential, -50 °C -58 °F, GRAS, UL listed electric tank, Fluid, Tank high limit

| Single-day Rating                    |  |  |  |  |
|--------------------------------------|--|--|--|--|
| Solar Fraction<br>(SF <sub>o</sub> ) |  |  |  |  |
| 0.67                                 |  |  |  |  |
|                                      |  |  |  |  |

Single-day Rating Conditions: SEF<sub>D</sub> = Solar Energy Factor (info link) SF<sub>D</sub> = Solar Fraction (info link)

| SINGLE DAY RATING CONDITIONS        | SI Units                     | Inch-Pound Units               |  |
|-------------------------------------|------------------------------|--------------------------------|--|
| System Set Temperature              | 57.2 °C                      | 135 °F                         |  |
| Environmental Temperature           | 19.7 °C                      | 67.5 °F                        |  |
| Ambient Temperature Profile Average | 14.4 °C                      | 58 °F                          |  |
| Water Mains Temperature             | 14.4 °C                      | 58 °F                          |  |
| Delivered Load                      | 43.3 MJ/day                  | 41,045 Btu/day                 |  |
| Solar Irradiance                    | 4,733 Wh/m <sup>2</sup> -day | 1,500 Btu/ft <sup>2</sup> -day |  |



| Storage Tank(s)                              |                      |  |  |  |
|--|----------------------|--|--|--|
| Solar Tank Vol (I)                           | Solar Tank Vol (gal) |  |  |  |
| 450  | 119                  |  |  |  |
| Approximate Collector Area: 5.9 m², 63.7 ft² |                      |  |  |  |

The solar water system listed here has been certified by the SRCC as meeting the minimum standards for testing, installation, operation, maintenance, performance, reliability and safety as specified in SRCC Document OG-300. Thermal performance ratings are based on the successful durability and performance testing of a sample collector, where said tests have been conducted by an independent laboratory approved and listed by the SRCC. The system has been modeled using the computer simulation program TRNSYS to calculate the ratings.

Before the Supplier can make any change in design, materials, specifications, parts, or construction, the change(s) must be reported to the SRCC for evaluation of continued certification.

**REMARKS:** 

Shawn Martin

Technical Director







SUPPLIER: HTP, Inc. 272 DUCHAINE BLVD NEW BEDFORD , MA 02745 USA www.htproducts.com

In Accordance with: SRCC OG-300-2001-10

BRAND: SOLAR SKIES

MODEL: PR-119-64-EB

SYSTEM TYPE: Pumped, Indirect

CERTIFICATION #: 2007019C

Original Certification:

February 14, 2008

Expiration Date: July 27, 2020

The solar system listed below has been evaluated by the Solar Rating & Certification Corporation™ (SRCC™), an ISO/IEC 17065 accredited and EPA recognized Certification Body, in accordance with SRCC OG-300, Operating Guidelines for Certifying Solar Water Heating Systems, and has been certified by the SRCC. This award of certification is subject to all terms and conditions of the Program Agreement and the documents incorporated therein by reference. This document must be reproduced in its entirety.

## Only the following options for the collector array are approved:

| Option | Collector Panel<br>Manufacturer | Collector Panel<br>Request<br>Number | Collector Panel<br>Model Number | Collector Panel<br>Name | Quantity | Total Panel area(m²) | Total Panel area(ft²) |
|--------|---------------------------------|--------------------------------------|---------------------------------|-------------------------|----------|----------------------|-----------------------|
| 1      | HTP, Inc.                       | 10001973                             | SS-32                           | Solar Skies             | 2        | 5.92                 | 63.72                 |

| Option | Collector Panel<br>Manufacturer | Collector Panel<br>Request<br>Number | Collector Panel<br>Model Number | Collector Panel<br>Name | Quantity | Total Panel area(m²) | Total Panel<br>area(ft²) |
|--------|---------------------------------|--------------------------------------|---------------------------------|-------------------------|----------|----------------------|--------------------------|
| 2      | HTP, Inc.                       | 10001918                             | SS-32-FP                        | Solar Skies             | 2        | 5.93                 | 63.87                    |

